

**Addendum No. 2**  
**March 26, 2018**

Project: Burgess Hall, Renovations  
University of South Dakota  
Vermillion, South Dakota  
OSE# R0618--28X

Architect: Architecture Incorporated

Letting: Wednesday, March 28, 2018  
3:00 PM CST  
Office of the State Engineer  
Joe Foss Building  
523 East Capitol  
Pierre, South Dakota 57501

Scope of this Addendum:

To all bidders and all others to whom drawings and specifications have been issued by Architecture Incorporated.

Acknowledge receipt of this addendum by listing its number and date in the bidders Form of Proposal. Failure to do so may subject bidder to disqualification. This Addendum forms a part of the Contract Documents. It modifies them as follows:

**GENERAL ITEMS:**

No Items

**MECHANICAL ITEMS:**

No Items

**ELECTRICAL ITEMS:**

1) SPECIFICATION SECTION – Interior Lighting 26 5100

- a) Page 5: See 3.3 Installation E. Suspended Ceiling Mounted Luminaires: 6. In Addendum #1, Delete the following: For areas where ceilings are being replaced.

2) DRAWING 9.10 First Floor Electrical Plan –

- a) First Floor Plan – Type F4 light fixture in Reception 134 shall be furnished with dimmable driver. See Addendum #1 for dimming control of light fixture in Reception 134.
- b) First Floor Plan – Existing light fixtures in Corridor 199 are supported by all threaded rod to the metal decking. Contractor to support new light fixture in same fashion. Provide threaded rod as required. Delete the following in Addendum #1: Type A & AE light fixtures in Corridor 199 to be clipped to the ceiling grid.

3) DRAWING 9.20 Electrical Details & Schedules –

- a) Light Fixture Schedule – Type F4, F4E and F8 light fixtures shall have 800 lumens per foot.

4) DRAWING 9.12 2<sup>nd</sup> & 3<sup>rd</sup> Floor Electrical Plan –

- a) Second Floor Plan – Existing light fixtures in Corridor 299 are supported by all threaded rod to the metal decking. Contractor to support new light fixture in same fashion. Provide threaded rod as required. Delete the following in Addendum #1: Type A & AE light fixtures in Corridor 299 to be clipped to the ceiling grid.
- b) Third Floor Plan – Existing light fixtures in Corridor 399 are supported by all threaded rod to the metal decking. Contractor to support new light fixture in same fashion. Provide threaded rod as required. Delete the following in Addendum #1: Type A & AE light fixtures in Corridor 399 to be clipped to the ceiling grid.

END OF ADDENDUM