Addendum No. 3
March 16, 2018

Project: **Lincoln High School – Window Replacement & Miscellaneous Renovations 2018 PD #3150**
Sioux Falls, South Dakota
Project No.: 2763

Architect: Architecture Incorporated

Letting: **Thursday, March 22, 2018**
2:00 PM
Central Services Center
1101 N. Western Avenue
Sioux Falls, South Dakota, 57104

Scope of this Addendum:

To all bidders and all others to whom drawings and specifications have been issued by Architecture Incorporated.

Acknowledge receipt of this addendum by listing its number and date in the bidders Form of Proposal. Failure to do so may subject bidder to disqualification. This Addendum forms a part of the Contract Documents. It modifies them as follows:

GENERAL ITEMS:

Register Grille & Diffuser Schedule: Add D1 diffusers

1) DRAWING SHEET – 8.10 – LEGEND, SCHEDULES AND DETAILS

   a) Register Grille & Diffuser Schedule: Add D1 diffusers to schedule per attached schedule below.

REGISTER GRILLE & DIFFUSER SCHEDULE

SYMBOL	MANUF.	CONSTR MAT"L	MODEL NO.	MAX CFM	OVERALL SIZE	THROAT SIZE	NC	THROW	TOTAL PD (IN.W.G.)	FRAME	PATTERNS	REMARKS
D1	KRUEGER	S	1400	230	24/24	8"%%C	26	12	0.08	LAY-IN	4-WAY	
G1	KRUEGER	A	EGC5	1000	24/12	22/10	25	---	0.08	LAY-IN	1/2" GRID	
G2	KRUEGER	A	EGC5	1400	24/24	22/22	15	---	0.03	LAY-IN	1/2" GRID	

LEGEND:
R - REGISTER
G - GRILLE
D - DIFFUSER

SD - SINGLE DEFLECTION
DD - DOUBLE DEFLECTION

A - ALUMINUM CONSTRUCTION.
S - STEEL CONSTRUCTION.

GENERAL NOTES:
1. THROWS ARE BASED ON TERMINAL VELOCITIES AT 50 FPM.
2. NC VALUES ARE BASED UPON A 10dB ROOM ATTENUATION.
3. SEE SPECIFICATIONS FOR OPPOSED BLADE DAMPER REQUIREMENTS.

REMARKS:

END OF ADDENDUM