

**Addendum No. 2  
January 28, 2019**

Project: **Beacom Hall 309 Renovation**  
University of South Dakota  
Vermillion, South Dakota  
Project No: 0927.2815.18

Architect: Architecture Incorporated

Letting: **February 7, 2019  
2:00 PM**  
University of South Dakota  
Purchasing Office  
209 Slagle Hall  
414 East Clark Street  
Vermillion, South Dakota 57069

Scope of this Addendum:

To all bidders and all others to whom drawings and specifications have been issued by Architecture Incorporated, this Addendum forms a part of the Contract Documents. Acknowledge receipt of this addendum by listing its number and date in the bidder's Form of Proposal. Failure to do so may subject bidder to disqualification. This addendum modifies the drawings and specifications as follows:

**GENERAL ITEMS:**

- 1) SPECIFICATION SECTION 012100 – ALLOWANCES
  - a) See attached specification section attached to the end of this addendum.
- 2) SPECIFICATION SECTION 084113 – ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS
  - a) Part 2.3.A.3 – Delete reference to Clear Anodized Finish. Finish of framing members to match existing which is Kawneer 70% Fluoropolymer Paint Finish 392x365 'Dove Grey'.
- 3) DRAWING SHEET 4.60 – FURNITURE PLAN
  - a) Refer to Supplemental Drawing SD-1 attached to the end of this addendum for revisions and additions to East Wall Elevation 2/4.60.

**MECHANICAL ITEMS:**

NA

**ELECTRICAL ITEMS:**

- 1) SPECIFICATION SECTION 271000 – STRUCTURED CABLING

- a) Page 3, Section 2.1 A.1. Manufacturers: Panduit is the only manufacturer allowed at USD. Eliminate “Hubbell Berk-tek, Hitachi, Belden, Mohawk, Commscope, and Allen Tel.”
- b) Page 4, Section 2.5 B. Wall Plates 3. Capacity: Add the following: “Data or Combination Voice/Data Outlets: 6 ports.”
- c) Page 4, Section 2.5 B. Wall Plates 4. Add the following: “Wall Plate Material/Finish – Flush Mounted Outlets: Match wiring device and wall plate finishes.”
- d) Page 4, Section 3.2 B. Conduit 4. Add the following: “Telecommunications conduit shall not be over 300 ft. in total distance from jack to rack.”
- e) Page 4, Section 3.2 B. Conduit 4. Add the following: “Conduit shall be 1 inch routed to accessible ceiling space with J-hooks to rack. Conduit shall be dedicated per box – no shared conduit between boxes.”
- f) Page 5, Section 3.3, Eliminate C. “Flood-Mounted Racks and Enclosures: Permanently anchor to floor in accordance with manufacturer’s recommendations.”

2) DRAWING SHEET 9.11 – ELECTRICAL PLAN

- a) Third Floor Electrical Plan –
  - i) For Panel L3A: Provide 22K AIC rated breaker to feed L3A2.
  - ii) At projection screen, add the following to Specific Note E204: “Provide hard wire connection to projection screen, mount j-box with stainless steel cover plate next to the projection screen end. Contractor to install a 90 degree MC coupling with a short whip from j-box with another 90 degree MC coupling at the end of projection screen.”
  - iii) At communication poles, add the following to Specific Note E201. “Contractor to terminate all sixteen (16) cables in the wall systems furniture. Pull cables through communications pole and provide grommet. Provide and install one (1) faceplate with two (2) jacks in wall panel for each table. Provide all mounting hardware as required and coordinate with systems furniture supplier.”
  - iv) At existing floor outlet for middle tables, add the following to Specific Note E304. “Provide patch cord from floor outlet to wall panel system. Cabling to route in wall panel system. Provide and install one (1) faceplate with two (2) jacks in wall panel for each table. Provide all mounting hardware as required and coordinate with systems furniture supplier.”
  - v) Labeling of data cables to be coordinated with USD IT Dept. Label to start clockwise in room from the main door. Label room number (309) with cable count at outlet starting with 01, 02, etc. for example 309-01, 309-02 for first floor outlet along the north row. Next floor outlet 309-03, 309-04. Ceiling data outlets shall be labeled C309 with cable count starting with 01, 02, etc.

3) DRAWING SHEET 9.12 – ELECTRICAL DETAILS & SCHEDULES

- a) Reference E-Floor Box Schedule – Add the following note to Floor Box # FB1 “Provide necessary adapter for Panduit jacks as required.”

**GENERAL APPROVALS:**

The following material or equipment furnished by the manufacturers listed, may be substituted as equivalent providing that each item, material, and piece of equipment conforms to the design and requirement of the specifications.

<u>SECTION</u>	<u>ITEM</u>	<u>MANUFACTURER</u>
26 5100	Interior Lighting Type F4	Mercury Architectural Ltg.
26 5100	Interior Lighting Type F4E	Mercury Architectural Ltg.
26 5100	Interior Lighting Type F8	Mercury Architectural Ltg.
26 5100	Interior Lighting Type X	Emergilite

END OF ADDENDUM